

Render zoom in of Plaza in context. Refer to Landscape Approach document for more information

[PT1]
STANDARD CARRIAGEWAY

Asphalt to SDCC standards

[PT2]
PAVED CARRIAGEWAY

Silver grey granite,
200x160x80mm, flamed finish
Technical build up to engineer detail

[PT3]
Pedestrian Footway Mix

Buff granite, sandblasted finish,
900x600mm
Silver grey granite, flamed finish,
900x600mm

[PT4]
Standard Footway

Proprietary block paving with
stone aggregate
600x300x50mm

[PT5]
Plaza Mix

700x300 & 300x150x50mm
Silver grey granite,lamed finish
Buff granite, sandblasted finish
Silver granite, flamed finish
Black granite, flamed finish

Plaza Planter Edge

Large Cut granite blocks

[PT6]
Heritage Mix 'Matts'

Buff granite, sandblasted finish,
900x600mm

Heritage inserts to PT6
Panelled insertions of contrasting material

-Canvas to receive historical interpretation
-Sandstone, corten, concrete for example

TREE

Existing

PLANTING

Mixed Herbaceous Planting

SMALL TREE

Proposed
Small tree or Large Shrub

TREE

Proposed
tree in ground

Benches

Wooden batton top on granite base.
Var dimensions

TREE

Proposed
Clearstem

Project: TALLAGHT VILLAGE ENHANCEMENT SCHEME	Client: SDCC	Drawing Title: Tallaght Village Landscape Plan	Drawing No: TVES-BSLA-ZZ-00-DR-L-003	Scale 1:500 @ A0	Status: PART 8 Revision: 00

Bernard Seymour Landscape Architects
The Capel Building
Mary's Abbey
Dublin 7
t +00 353 1 8747764
e info@bslarch.com